

No	Description of Item	Unit	No	L	B	D	Qty	Rate	Amount
3	KSRRB M400- Wet Mix Macadam - KSRRB M400-17 Providing, laying, spreading and compacting graded stones aggregate to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. MORTH Specification No. 406 (P No.158 I.No.20.18) Sr 2018-19	Cum							
	From Ganesh Theater 3rd A cross junction		2	93.00	4.00	0.20	148.80		
	S Bank to Allalasandra lake 80 feet road A sector		2	425.00	1.50	0.20	255.00		
			2	130.00	1.50	0.20	78.00		
							481.80	2001.28	964217.00
	Basic Rate	1888.00							
	Area Weightage 6%	113.28							
	Grand Total	2001.28							
4	Providing and applying primer coat with ss bitumen emulsion on prepared surface of granular base such as WMM including clearing of road surface and spraying primer at the rate of 0.60 kg/sqm using mechanical means complete as per specifications. MORTH Specification No. 502 (P.No.160/lt No.21.6) SR 2018-19	sqm							
			1	97.40	18.50		1801.90		
			1	650.00	2.55		1657.50		
			1	120.00	17.50		2100.00		
							5559.40	36.04	200361.00
	Basic Rate	34.00							
	Area Weightage 6%	2.04							
	Grand Total	36.04							

No	Description of Item	Unit	No	L	B	D	Qty	Rate	Amount
5	KSRRB M500-17. Providing and laying dense graded bituminous macadam using crushed aggregates of specified grading, premixed with VG30 grade bituminous binder and, transporting the hot mix to work site, laying to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction in all respects complete as per specifications. Clause 505 of MORTH V revision. - do - using 40/60 TPH capacity H.M.P. with Mechanical paver Gr-II (50 mm to 75 mm) with 4.5 % VG-30 Bitumen (P.No.160 lt.No.21 17.6) KPWD SR 2018-19	cum							
			1	97.40	18.90	0.050	92.04		
			1	645.00	2.50	0.050	80.63		
			1	120.00	17.50	0.050	105.00		
							277.67	7721.04	2143886.00
	Basic Rate	7284.00							
	Area Weightage 6%	437.04							
	Grand Total	7721.04							
6	KSRRB: 500-2 : Cleaning the existing black topped surface with brooms, soft brushes and finally dusting with old gunny bags and /or compressed air to receive bituminous treatment including cost of all materials, labour, HOM of machineries complete as per Specifications. (P.No.157 & I.No.21.2) KPWD SR 2018-19	Sqm							
			1	97.40	18.50		1801.90		
			1	650.00	14.00		9100.00		
			1	120.00	17.50		2100.00		
							13001.90		
	deduction		1	425.00	0.250		106.25		
							12895.65	5.30	68347.00
	Basic Rate	5.00							
	Area Weightage 6%	0.30							
	Grand Total	5.30							
7	KSRRB 500-7: Providing and applying tack coat using 85/150 grade bitumen(VG10) on the prepared black topped surfaces at 2.5 kg per 10 sqm, heating bitumen in boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour, HOM complete as per specifications. Clause 503 of MORTH V revision (P.No.158 & I.No.21.7) KPWD SR 2018-19	sqm							
			1	97.40	18.50		1801.90		

[illegible]

No	Description of Item	Unit	No	L	B	D	Qty	Rate	Amount
	Miscellaneous charges								944.33
	Total								10000000.00

(Rupees Hundred Lakhs Only)

CERTIFICATE

- 1 The work spot has been inspected and the work is found necessary.
- 2 This estimate is prepared as per P.W.D of 2018-19
- 3 The provisions were made in this estimate are necessary and adequate.
- 4 This works come under B.B.M.P. limits.

Assistant Engineer
Ward No.04

Executive Engineer
Yelahanka Division
Bangalore-64

Assistant Executive Engineer
Yelahanka Satellite town Sub Division
Bangalore-64

Administrative Sanction for Rs. 100.00 Lakh
Hundred Lakh only

is accorded under head P. 3521
- 2018-19


Registered as CE No. Subject
to conditions contained in enclosed memo
No. EE/AA/H4/18-19 Dr. 2.3.19

Technical Sanction
Accorded For Rs. 100.00 Lakh only
Head of A/C P. 3521
CER NO. 224 Dt. 02.03.19

TA CE (YNK)

Name of work: Improvements to roads and drains at A Sector main and cross roads in ward no -04.

Hale
reche
lake



INDEX: Proposed
 Asphalt
 work

A.E. Ramrajewar

A.E.E.